

Test Report

Report Number:140618003SHJ-BP-3

Applicant Name: Zap Supplies LLC (Permshield)

Original Report Date: July 8, 2014

Applicant Address: 1800 N Powerline Rd #5,
Pompano Beach, FL USA 33069

Attn: Paulo Lins

Sample Description:

Product: 1.5mm IXPE

Model: HX-15(66KGS)

Samples Quantity: 15m²

Sample ID: S140618003SHJ-001~021

Date Received: 2014-06-17

Date Test Conducted: 2014-06-18~2014-07-08

Tests Conducted:


Test Methods: ASTM E492-09, ASTM E989-06, ASTM E2179-09

Conclusion:

For details refer to attached page(s).

The conclusions of this test report may not be used as part of the requirements for Intertek product certification.
Authority to Mark must be issued for a product to become certified.

Should you have any queries about the test report, please contact:

Approved by:**Checked by:****Prepared by:**Dorian Wu
SupervisorJodie Zhou
Technical SupervisorEric Zhu
Engineer

Test Items, Method and Results:

Test Method: ASTM E492-09


Temperature: 25°C

Relative Humidity: 65%

Specimen area: 12.8m²

Volume of the receiving room: 121m³

Floor/ceiling Assembly: The system consisted of 150mm thick concrete floor which had a 1.5 mm sound insulation pad installed on the top of it. The 5mm flooring specimens were then placed on the top of the insulation pad.



Calculated Impact Insulation Class: IIC71

Note:

1. L_n = Normalized Sound Pressure Level for Covering over Floor/ceiling System
2. Classified IIC in accordance with ASTM E989-12, Standard Classification for Determination of Impact Insulation Class.
3. The IIC was for the whole floor/ceiling assembly system.

Test Method: ASTM E90-09


Temperature: 25°C

Relative Humidity: 65%

Specimen area: 12.8m²

Volume of the receiving room: 121m³

Floor/ceiling Assembly: The system consisted of 150mm thick concrete floor which had a 1.5 mm sound insulation pad installed on the top of it. The 5mm flooring specimens were then placed on the top of the insulation pad.



Calculated Sound Transmission Class: STC 69

Note:

1. TL= Transmission loss, the partition was the Floor/ceiling Assembly System.
2. Classified STC in accordance with ASTM E413-10, Classification for Rating Sound Insulation.
3. The STC was for the whole floor/ceiling assembly system.

Appendix A: Sample photos



Test setup

The End of Report

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.